SHIMOGA DIVISION.

Notification dated 7th July 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 4 P.M., on 25th July 1938, for Restoring Induvalli Hosakere Reg. No. 512 of Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and twenty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Induvalli Hosakere Reg. No. 512 of Sorab Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage loss or more than estimated rate will not be accepted.

13. The successful tenderer will have to deposit another sum of Rs. 122 towards the security deposit before the execution of contract agreement.

Abstract estimate for restoring Induvally Hosakere, Register No. 512 of Sorab Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	Bund.				
1	Jungle clearing	Grades		13	
2	Earthwork to bund with watering and tamping, etc., with ½' gravel at top including lead	C.yd.	0 5 0	4,202	
3	Turfing to Bund	Sqr.	0 8 0	328	
4	Providing and fixing grade stones including carving figures and painting, etc., with zero stone	Each	2 0 0	13	
5	Do Index stones	,,	1 0 0	13	
6	Do B. M. stones	,,	3 0 0	2	
7	Do Register No. and date stone	,,	3 0 0	1	
8	Do Sluice and C detail stone	,,	10 0 0	1	
	Waste Weir.				
1	Earthwork excavation of foundation in hard soil	C.yd.	0 4 0	70	
2	Cement concrete 1 : 4 : 8	C.ft.	0 7 0	234	
3	Cut laterite stone in cement mortar 1 : 6	,,	0 6 0	456	
4	New laterite stone work for revetment with 1 mile lead	C.yd.	2 8 0	70	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
5	Draft and approach clearing and using the earth for improving the flank bund at the right side of the weir	L. S.	..	..	
6	Providing a piped vent of 6" dia. at the centre of the weir at R. L. 49·00	"	..	..	
	Sluice at C.S. 9 at R.L. 49.00.				
1	Earthwork cutting open the bund and refilling with watering consolidation	C.yd.	0 3 6	64	
2	Concrete in cement mortar 1 : 5 : 10	C.ft.	0 6 0	188	
3	Cut laterite in cement mortar	"	0 6 0	149	
4	Burnt stone slabs 4½" to 6" thick dressed and fixed in mortar	S.ft.	1 0 0	26	
5	Cutting holes in slabs	Each	1 0 0	3	
6	Providing plug with iron rod with locking arrangement, etc.	"	10 0 0	1	
7	New laterite stone revetment work with 1 mile lead.	C.yd.	2 8 0	16	
8	Providing 6" dia. C.I. pipe including carting and fixing with cement joints at junction	R.ft.	3 8 0	30	

P. SUBBA RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 11th July 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 6th August 1938, for Protective works to Kallahalli Tank, Reg. No. 22 of Chitaldrug Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 180 (one hundred and eighty only) which should be credited to the Treasury and the Treasury Challan enclosed as earnest money and be superscribed "Tender for Protective works to Kallahalli Tank, Reg. No. 22, Chitaldrug Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.